



PROJECT SHEET

Paving Joint Work

SAINT-CIRQ-LAPOPIE, FRANCE

THE PROJECT

With a history spanning over 2,000 years, the village of Saint-Cirq-Lapopie is listed among the Most Beautiful Villages of France and welcomes 700,000 visitors

annually. The municipality undertook a complete renovation of squares and streets, replacing 5,000 m² of asphalt with locally sourced stone paving.



Owner

Commune of St-Cirq-Lapopie

Architect

Juliette FAVARON

Contractor

Occitanie Pierres

Duration

18 months over 30 months

Delivery date

Spring 2020



TECHNICAL APPROACH

Paving bed

Bedding layer in CEM II 32.5 cement mortar

Pavement joints

→ For high-stress areas:

Total binder: 385 kg/m³, including 40% CNP

Mix: 140 L of 0/4 sand + 35 kg CEM 32.5 + 20 kg CNP (approx. 2 buckets)

→ For low-stress areas:

Total binder: 385 kg/m³, including 40% CNP

Mix: 140 L of 0/4 sand + 35 kg CEM 32.5 + 20 kg CNP (approx. 2 buckets)

Optional: TEMPO retarder can be used to adjust setting time.



VICAT ADVANTAGES

- Color of PROMPT natural cement
- Technical support for the client in mix formulation




PERFORMANCE REQUIREMENTS



Natural ochre color for aesthetics



Rapid setting and hardening



For more information, contact Jean-Philippe Bruasse, Technical Trainer & Advisor PROMPT:

jean-philippe.bruasse@vicat.fr
ciment-prompt-vicat.fr